

State of Kansas



15-203-20012-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this
date requested permission to plug the following described well:Mr. Flemmons guarantees payment of the plugging fee.Operator's full Name: Jerry D. Fouts or Catcus Operating Company,Complete Address: 918 Lamar Street, Wichita Falls, Texas.Lease Name: Kessler Well No. 1Location: App: C of Sec. 18 Twp. 18 Rge. (E)(W) 35County: Wichita Total Depth 2835' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Flemmons was instructed to plug the well as follows:350'--8 5/8" Surface casing, cement circulated.2775'--7" OD casing cemented on bottom with 125 Sx. Open hole completion.Set 7" wire line bridge plug below top of cement with 6' cement on top.
Shoot off 7" casing, pull 1 joint and displace cement thru 8" casing to
base of surface. Pull 7" casing set bridge and 10' cement to bottom of
cellar.

Very truly yours,

Conservation Division Agent