



15-203-20006-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 APR 11 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Leo Swords of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: Davidor & Davidor, Incorporated,

Complete Address: 4515 North Santa Fe, Oklahoma City, Oklahoma.

Lease Name: Everett Caldwell Well No. B-1

Location: NW-SW Sec. 34 Twp. 20 Rge. (E)(W) 38

County: Wichita Total Depth 4915' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Swords was instructed to plug the well as follows:

320'--8 5/8" Surface pipe, cement circulated with 225 Sx.
Top of Dakota Section @ 800'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx.
cement thru DP. Pull DP to 330' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent