

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20431-00-00
Spot: NENENE Sec/Twnshp/Rge: 25-17S-31W
4940 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: VON SCHRILTZ Q Well Number: 1
County: SCOTT Total Vertical Depth: 4610 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: 201 W ASH PO BOX 544
NESS, KS 67560

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 326 WITH 185 SX CMT
Production: Size 4.5 feet: 4608 WITH 150 SX CMT
Liner: Size _____ feet: 149.83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2000 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: SAND OFF BOTTOM PERFS & DUMP 2 SX CMT. WITH A DUMP BAILER. TIE ONTO 4-1/2 & CMT PERFS @ 4267 & GEL SPACER TO 2000. FILL PIPE TO SURFACE & CHECK BACKSIDE OF 8-5/8.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/22/2000 10:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFORATED AT 1550' SQUEEZED WITH 300 SX CMT. PERFS AT 4267-69, 4544-48, & 4524-26'. PRESSURED UP 8 5/8" X 4 1/2" ANNULUS TO 500#. CMT AT SURFACE. PUMPED DOWN 4 1/2" 50 SX CMT WITH 400# HULLS, 10 SX GEL, 120 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 1000#.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 02 2001

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

INVOICED

DATE 1/3/00

INV. NO. 2001061235

DEC 26 2000