

1 090423

5-11

API NUMBER 15- 171-20,368 -00-02

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
206 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SE, SEC. 25, T. 17 S, R. 31
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Brungardt Well # 1

Operator: Chief Drilling, Inc.

County Scott 150.15

Name & Address 120 S. Market, Ste. 300

Well Total Depth 4620 feet

Address Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 120 S. Market, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 11 Month: 5 Year: 19 94

Plugging proposal received from Gary Lindenmuth
(company name) Chief Drilling, Inc. (phone) 316-262-3791

Perfs: 4 1/2" at 4615' w/200 sx cement, PBTD 4403', Perfs at 4536-38, 4528-32, 4520-22, 4362-65'
1st plug pump 3 sx hulls with 200 sx 65/35 Pozmix 8% gel down 4 1/2",
2nd plug pump 150 sx cement down backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 11 Month: 5 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls with 200 sx cement down 4 1/2" casing.

Maximum pressure 1300 psi and shut in 500 psi.

2nd plug hooked onto backside and pumped in 150 sx cement.

Maximum pressure 300 psi and shut in 0 psi.

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 5-24-94

Signed _____ (TECHNICIAN)

INV. NO. 40483