

1 050683

API NUMBER 15-171-20,307-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE, SEC. 24, T. 17 S, R. 31 W/E

2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Van Dolah Well # 1

Operator: Petroleum Inc.
Name & Address: 300 W. Douglas
Suite 800
Wichita, KS 67202

County Scott 149.83
Well Total Depth 4670 (Miss) feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 218'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc License Number 5422

Address 801 Union Center Wichita, KS 67202

Company to plug at: Hour: 12:10 am Day: 15 Month: November Year: 19 85

Plugging proposal received from Wayne Shively

(company name) Abercrombie Drilling Inc (phone) 316-262-1841

were: keep hole full of heavy mud + spot cement plugs
through drill pipe. 1st plug @ base of the Anhydrite
w/50sx. 2nd plug @ 1230' w/70sx, 3rd plug
@ 240' w/50sx, 4th plug @ 40' w/solid Bridge Plug
+ 10sx Circulate Rathole w/15sx of cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 am Day: 15 Month: November Year: 19 85

ACTUAL PLUGGING REPORT kept hole full of heavy mud + spotted
cement plugs through drill pipe. 1st plug @ 2301'
with 50sx. 2nd plug @ 1230' w/70sx 3rd plug
@ 240' w/50sx 4th plug @ 40' w/solid Bridge Plug
+ 10sx. Circulate rathole w/15sx cement.

Anhydrite (2280-2301) Elevation 2899 GL

Remarks: Halliburton pumped 60/40 pozmix 6% gel cement
(if additional description is necessary, use BACK of this form.)

INVOICED RECEIVED STATE CORPORATION COMMISSION

DATE 12-9-85

NOV 18 1985

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 11320

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84