

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20509-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 28-17S-32W
330 feet from N Section Line, 2310 feet from E Section Line
Lease/Unit Name: ERSKIN A Well Number: 1-28
County: SCOTT Total Vertical Depth: 4790 feet

Operator License No.: 4243
Op Name: CROSS BAR PETROLEUM, INC.
Address: 7570 W. 21ST. BLDG 1014, STE. B
WICHITA, KS 67205

Conductor Pipe: Size feet: 3 1/2 5.68
Surface Casing: Size 8.625 feet: 430 WITH 225 SX CMT
Production: Size 5.5 feet: 4784 WITH 125 SX CMT
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 03/05/2002 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: CIBP @ 4003'. PERFORATE CASING AT 2045'. PUMPED DOWN 5 1/2" 300# HULLS & 185 SX CMT. PRESSURE TEST. PUMP DOWN ANNULUS AND PRESSURE CHECK.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/05/2002 9:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 4630-36, CIBP @ 4480', 4331-35, CIBP @ 4003'. PORT COLLAR @ 2320' WITH 150 SX CMT TO SURFACE. CIBP SET AT 4003'. PERFORATED CASING AT 2045'. PUMPED DOWN 5 1/2" 300# HULLS & 185 SX CMT. MAXIMUM PRESSURE 1800#. SHUT IN PRESSURE 1100#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS PRESSURED UP TO 500#. CMT AT SURFACE.

RECEIVED
MAR 11 2002
KCC WICHITA
03-11-2002

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED
DATE Mar 12-02
INV. NO. 2002061510

MAR 06 2002



Handwritten initials