

1090964

TO: STATE CORPORATION COMMISSION

10-29

API NUMBER 15-171-20,508-00-00
NE SW SEC. 28, T 17 S, R 32 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME FREED WELL # 1-28

TECHNICIAN'S PLUGGING REPORT COUNTY SCOTT 196.22

OPERATOR LICENSE # 3842 WELL TOTAL DEPTH 5422' FEET

OPERATOR: LARSON OPERATING PRODUCTION CSG: SIZE 5 1/2" @ 4722' WITH 175 SX

NAME AND 562 WEST HIGHWAY 4 SURFACE CASING: SIZE 8 5/8" @ 409' WITH 240 SX

ADDRESS OLMITZ, KS 67564-8561

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31, RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 2:15 PM DAY: 29 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM TOM LARSON

(COMPANY NAME) LARSON OPERATING (PHONE) 316-653-7368

WERE: PORT COLLAR AT 2325' WITH 195 SX CEMENT.

PORT COLLAR @ 2325'. CEMENT TO SURFACE WITH 195 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:15 PM DAY: 29 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

ALLIED PUMPED DOWN 5 1/2" CASING WITH 35 SX CEMENT, 3 HULLS, 20 SX GEL, 170 SX CEMENT.

PUMP PRESSURE AT 1500#. SHUT IN AT 500#. BACKSIDE NO CEMENT. PRESSURE TO 500 PSI.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

RECEIVED
M.A. CORP
10-30-98
2:57

[Handwritten mark]

60256