

1080257

TO: STATE CORPORATION COMMISSION

8-13

API NUMBER 15-171-20,537-00-00  
NW NW SE SEC. 28, T 17 S, R 32 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME NEWELL UNIT WELL # 1-28

TECHNICIAN'S PLUGGING REPORT COUNTY SCOTT

OPERATOR LICENSE # 3842 WELL TOTAL DEPTH 4061' 131.98 FEET

OPERATOR: LARSON OPERATING PRODUCTION CSG: SIZE @ WITH SX

NAME AND 562 WEST HIGHWAY 4 SURFACE CASING: SIZE 8 5/8 @ 365' WITH SX

ADDRESS OLMITZ, KS 67564-8561

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR L.D. DRILLING, INC LICENSE NUMBER 6039

ADDRESS RR 1, BOX 183-B GREAT BEND, KS 67530-0183

COMPANY TO PLUG AT: HOUR: 7:15 PM DAY: 13 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DORAN MARGHEIM

(COMPANY NAME) L.D. DRILLING (PHONE) 316-793-3051

WERE:

1ST PLUG AT 2340' WITH 50 SX CEMENT. 2ND PLUG AT 1500' WITH 80 SX CEMENT.

3RD PLUG AT 700' WITH 30 SX CEMENT. 4TH PLUG AT 390' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

NO MOUSE HOLE. PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 PM DAY: 13 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG AT 2340' WITH 50 SX CEMENT. 2ND PLUG AT 1500' WITH 80 SX CEMENT.

3RD PLUG AT 700' WITH 30 SX CEMENT. 4TH PLUG AT 390' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

NO MOUSE HOLE.

REMARKS: USED 60/40 POZMIX 6% 1/4# FLO SEAL BY ALLIED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED [Signature] RECEIVED [Signature]  
(TECHNICIAN) FORM CP-2/3

DATE 8-24-99

AUG 20 1999  
08-20-1999  
CONSERVATION DIVISION  
Wichita, Kansas

WV. NO. 60370

2