

1050228

171-30002-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Unknown

C SW/4, SEC. 35, T 19 S, R 33 W/R

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6814

Lease Name Smith Well # 1-35

Operator: Cargill, Inc.

County Scott

Name & Address Box 8292C

Well Total Depth 2654 86.26 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 17 Month: May Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2348

were: 4 1/2 set at 2654 Perf 2530'

1st plug sand back to 2580 and dump 5 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 225 sx cement.

Plugging Proposal Received by Richard W. Lacy (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 17 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 2654' Perf 2530'

1st plug sanded back to 2580' and dumped 5 sx cement on top of sand

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pumped an additional 225 sx cement.

Maximum pressure 400# and shut in pressure 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 1022' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 5-25-84

STATE CORPORATION COMMISSION

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 1652

MAY 23 1984

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84