

1 090018

8-15

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,380 - 00-00  
C NW NW, SEC. 35, T 19 S, R 33 W/E

4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8247

Lease Name Smith Well # 1

Operator Name: Robert F. Hembree

County Scott 154.38

Address P.O. Box 458

Well Total Depth 4750 feet

Ness City, KS 67560

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service Inc. License Number 6907

Address P.O. Box 458, Ness City, KS 67560

Company to plug at: Hour: 9:30 a.m. Day: 15 Month: 8 Year: 19 89

Plugging proposal received from Fred J. Hembree

(company name) Hembree Well Service Inc. (phone) 316-798-3408

were: 4 1/2" at 4387' PBTD 4390' Perfs at 4271'

1st plug sand back to 4220' and dump 4 sx cement on top of sand through bailer

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1989  
08-18-89  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:20 a.m. Day: 15 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded to 4220' and dumped 4 sx cement on top of sand using dump bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2519' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(customer) observe this plugging.

DATE 8-24-89

Signed Michael R. Wilson (TECHNICIAN)

INV. NO. 25733

8-15