

1 061143

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,377-06-00

SE NE, SEC. 35, T 19 S, R 33 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399
Operator: American Energies Corporation
Name & Address: 155 North Market, Suite 710
Wichita, KS 67202

Lease Name Smith "J" Well # 1
County Scott 151.78
Well Total Depth 4670 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5886
Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 2:30 a.m. Day: 14 Month: 10 Year: 19 88

Plugging proposal received from Marrion Burris

(company name) Warrior Drilling Company (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2164-83'

- 1st plug at 2180' with 50 sx cement.
- 2nd plug at 1330' with 80 sx cement,
- 3rd plug at 430' with 50 sx cement,
- 4th plug at 40-0' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:45 a.m. Day: 14 Month: 10 Year: 19 88

- ACTUAL PLUGGING REPORT
- 1st plug at 2180' with 50 sx cement,
 - 2nd plug at 1330' with 80 sx cement,
 - 3rd plug at 430' with 50 sx cement,
 - 4th plug at 40-0' with 10 sx cement,
 - 5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10-17-88
OCT 17 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED ~~did not~~ observe this plugging.

DATE 10-19-88
INV. NO. 22593

Signed Paul A. Luthi
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 10... 3... 88... month day year

API Number 15-171-20,377-0000

OPERATOR: License # 5399 Name American Energies Corporation Address 155 N. Market, Suite 710 City/State/Zip Wichita, KS 67202 Contact Person Alan L. DeGood Phone 316-263-5785

SE NE Sec. 35 Twp. 19 S. Rg. 33 East 3300 West 660 Ft. from South Line of Section 660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet County Scott

Lease Name Smith "J" Well # 1

Ground surface elevation 2950 feet MSL

Domestic well within 330 feet yes X no

Municipal well within one mile yes X no

Depth to bottom of fresh water 250'

Depth to bottom of usable water 1450' 1500'

Surface pipe by Alternate 1 2 X

Surface pipe planned to be set 375'

Conductor pipe required None

Projected Total Depth 4750 feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventuality plugging hole to KCC specifications.

Date 9-26-88 Signature of Operator or Agent Alan L. DeGood Title Vice-President

Well Drilled For: X Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200' feet per Alt. X 2 This Authorization Expires 3-27-89 Approved By 2KM 9-27-88

EFFECTIVE DATE: 10-2-88

10-4-4:00 375+85/8

Now well

SE NE Sec. 35 Twp. 19 S. Rg. 33 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Casing (feet of, sx). Includes rows for 1st through 5th plugs and Rathole/Mousehole to surface minus 5 feet.

Vertical list of well parameters: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG, 2nd PLUG, 3rd PLUG, 4th PLUG, RAT HOLE CIRCULATED W/, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/, CEMENT COMPANY, TECHNICIAN.

RECEIVED STATE CORPORATION COMMISSION OCT 17 1988 CONSERVATION DIVISION Wichita, Kansas