

To: 1080005
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 171-20,272-00-00
SW SE, SEC. 32, T 19 S, R 33 W/E

12-15

660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5210

Lease Name Bontrager Well # 1-32
County Scott

Operator: Lebsack Oil Production, Inc.
Name:
Address P.O. Box 489
Hays, KS 67601

Well Total Depth 4800 156.00 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 421

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 15 Month: 12 Year: 1995

Plugging proposal received from Wayne Lebsack
(company name) Lebsack Oil Production (phone) 913-625-5444

Work: 5 1/2" at 4799' w/185 sx cement, Perfs at 4698-4702, 4671-85, 4252-58, 4202-08'

1st plug sand back to 4150' and dump 5 sx cement on top of sand through bailer.

2nd plug at 1300' with 80 sx cement,

3rd plug at 450' with 50 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 21 1995

12-21-95
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 15 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 9 sx gel, 80 sx cement, and 8 sx gel at 1300',

3rd plug pulled up to 450' and pumped 6 sx gel, 50 sx cement,

4th plug pulled up to 40' and circulated hole with 30 sx cement. Hole stayed loaded.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2021' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-8-96
INV. NO. 44445

Signed Kevin D. Shuck
(TECHNICIAN)