

1 030746

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,278-00-00
SE/4, SEC. 32, T 19 S, R 33 W/E
510 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210
Operator: Lebsack Oil Production, Inc.
Name & Address P.O. Box 489
Hays, KS 67601

Lease Name Kaufman Well # 1-32
County Scott "156.00"
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:40 p.m. Day: 22 Month: 9 Year: 19 86

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-534-3635

were: 4 1/2" at 4799' Perfs at 4700-08 & 4660-68

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 75 sx cement, 10 sx gel, 150 sx cement

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:20 p.m. Day: 22 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 75 sx cement, 10 sx gel, 150 sx cement

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Recovered 2500' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 9-26-86

09-26-86
SEP 26 1986

Signed Steve Duntz
(TECHNICIAN)

INV. NO. 15021