

1 050382

15-171-20282-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,282-00-00

SE SW, SEC. 32; T 19 S, R 33 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Keyse Well # 1-32

Operator: Lebsack Oil Productions, Inc.
Name & Address: P. O. Box 489
Hays, KS 67601

County Scott 154.70

Well Total Depth 4760 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5:00 pm Day: 8 Month: November Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4759'

1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 175 sx cement.

CLYDE WILEY WENT TO THE WELL AND SAW THE PLUGGING

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:30 pm Day: 8 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4759'

1st plug sanded back to 4700' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 175 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc

NOV 20 1984
11-20-84
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

Clyde Wiley
(did / ~~not~~) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 12-3-84
INV. NO. 5752