

To: 1 070306
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,354-00-00
C W/2 W/2 ^{NW} SEC. 28, T 19 S, R 33 W/8
3960 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Geeseka Well # 1

Operator: Lebsack Oil Production, Inc.
Name & Address P.O. Box 489

County Scott 154.70

Wichita, KS 67202 *Hays, KS 67601*

Well Total Depth 4760 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 394

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12 a.m. Day: 15 Month: 2 Year: 19 87

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 913-674-5768

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2200-25'
1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1300' with 80 sx cement,
3rd plug at 30' below surface pipe with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2 a.m. Day: 15 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2225' with 50 sx cement,
2nd plug at 1300' with 80 sx cement,
3rd plug at 425' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel, 3% cc by B.J. Titan.
(If additional description is necessary, use BACK of this form)

INVOICED

DATE 2-19-87
INV. NO. 16155

Signed Dan Gooden (TECHNICIAN)
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

2

Starting Date 2-3-87 month day year

API Number 15-171-20,354-00-00

OPERATOR: License # 5210 Lebsack Oil Production, Inc. P. O. Box 489 Wichita, KS 67202 Contact Person: Rex Curtis Phone: 913-625-3046

C W/2 W/2 NW Sec. 28 Twp. 19 S, Rg. 33 East West 3960 4950 Ft. from South Line of Section Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422 Name: Abercrombie Drilling, Inc. City/State: Wichita, KS 67202

Nearest lease or unit boundary line 330 feet County: Scott Lease Name: Geeseka Well #: 1 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1-2 X Depth to bottom of fresh water: 200 Depth to bottom of usable water: 1000 1225 Surface pipe planned to be set: 350 Projected Total Depth: 4700 feet Formation: Morrow

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 1-30-87 Signature of Operator or Agent Title: Agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 7-30-87 Approved By 1-30-87

Set 350' of 8 5/8" on 2/4/87

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, casing size, and cement/gel specifications. Includes entries for Base Anhydrite, Base Cheyenne/Dakota, 30' below surface, Top 40', and Rathole with 15'.

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.

Handwritten notes: PUSHER Harold Mailey, TD 4760' FORMATION MISS, SURFACE PIPE 8 5/8" @ 394', ANHYDRITE 2200-25' ELEVATION N/A, STARTING TIME & DATE 12:00 AM 2-15-87, COMPLETION TIME & DATE 2:00 AM 2-15-87, 1st PLUG @ 2225' FT. W/ 50 SX, 2nd PLUG @ 1300 FT. W/ 80 SX, 3rd PLUG @ 425 FT. W/ 50 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY B.J. Titan, TECHNICIAN Dan Goodrow, Sawmire, 60/40 pos., 6% gel, 3% CC

STATE CORPORATION COMMISSION

FEB 18 1987

CONSERVATION DIVISION Wichita, Kansas