

To: 1 071071
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-2
API NUMBER 15- 171-20,447-00-00 38
100' N of
SE SE NW, SEC. 27, T 19 S, R 33 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drilling, Inc.
Name & Address
120 S. Market, Suite 300
Wichita, KS 67202

3070 feet from S section line

2970 feet from E section line

Lease Name Vulgamore Well # 1-27 Twin

County Scott 140.40

Well Total Depth 4320 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 120 S. Market, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 2 Month: 6 Year: 19 92

Plugging proposal received from Harold Dinkle

(company name) Chief Drilling, Inc. (phone) 316-272-3791

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2172-90'

1st plug at 2190' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,

3rd plug at 270' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8 a.m. Day: 2 Month: 6 Year: 1992

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement,

2nd plug at 1500' with 80 sx cement,

3rd plug at 270' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1992

~~Observe~~ (did not) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

DATE 6-30-92

INV. NO. 35585

EFFECTIVE DATE: 5-25-92

DISTRICT # 1
SGA? Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 171-20,447-00-00

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 5-24-92
month day year

Spot
100' N. SE SE NW Sec 27 Twp 19S S, Rg 33W East West

OPERATOR: License # 5886
Name: Chief Drilling, Inc.
Address: 120 S. Market, #300
City/State/Zip: Wichita, Kansas 67202
Contact Person: Douglas W. Thimesch
Phone: 316.272-3791

3070 FSL feet from South / North line of Section
2970 FEL feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Scott
Lease Name: Vulgamore Well #: #1-27 Twin
Field Name: unnamed

CONTRACTOR: License #: 5886
Name: Chief Drilling, Inc.

Is this a Prorated/Spaced Field? yes ..X no
Target Formation(s): LKC
Nearest lease or unit boundary: 330

Well Drilled For: Well Class: Type Equipment:
X ... Oil ... Enh Rec ... Infield ..X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... O/W/O ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Ground Surface Elevation: n/a feet MSL
Water well within one-quarter mile: yes ..X no
Public water supply well within one mile: yes ..X no
Depth to bottom of fresh water: 200
Depth to bottom of usable water: 1300

If O/W/O: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Surface Pipe by Alternate: 1 ..X 2
Length of Surface Pipe Planned to be set: 250
Length of Conductor pipe required: 0

Directional, Deviated or Horizontal wellbore? yes ..X no
If yes, true vertical depth:
Bottom Hole Location:

Projected Total Depth: 4700
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well farm pond X.. other

DWR Permit #:
Will Cores Be Taken?: yes X.. no
If yes, proposed zone:

AFFIDAVIT

220' Alt. II Req.

Exp. 11/20/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Harold Duke
SPUD DATE 5-22-92 INIT. RWL
LENGTH SURFACE PLANNED 230-8 1/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/4 @ 253' CONDUCTOR
ANHYDRITE T- 2172 B- 2190 ELEVATION
TD 4320 FORMATION M/M.
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2190 Ft. W/ 50 SX
1/2 Base Anhy. @ 1500 Ft. W/ 80 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 270 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond)
Hauling
TECHNICIAN DG DATE 6-1-92 eye
TYPE OF CEMENT 60/40 per 6' gal
START TIME 12:00 (AM/PM) DATE 6-2-92
COMPLETION TIME 5:00 (AM/PM) DATE 6-2-92
CEMENT COMPANY Allied
STATE CORPORATION COMMISSION
Wichita, Kansas