

1050223

15-171-30003-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 3-9-65

C W/2 W/2 SW SEC. 26, T 19 S, R 33

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6814

Lease Name Smith Well # 1-26

Operator: Cargill, Inc.

County Scott

Name & Address Suite 604, One Main Place

Well Total Depth 2685 87.26 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 4:00 pm Day: 17 Month: May Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316-938-2348

were: 4 1/2 set at 2677' Open hole completion

1st plug sand to 2627 and dump 4 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 1 sack hulls and release

8 5/8" rubber plug and pump an additional 225 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 pm Day: 17 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 2677' Open hole completion

1st plug sanded to 2627' and dumped 4 sx cement on top of sand

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 1 sack hulls and released

8 5/8" rubber plug and pumped an additional 225 sx cement.

Maximum pressure 800# and shut in pressure a good 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

(If ~~it is~~ necessary) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 5-25-84

INV. NO. 11653