

9-2615-171-20017-00-00 202

To: 1 070983
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-19,086
150' N of
C SW SW, SEC. 26, T 19 S, R 33 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234
Operator: Petroleum Production Management
Name &
Address 200 Sutton Place
Wichita, KS 67202

810 feet from S section line
4620 feet from E section line
Lease Name Smith Well # 8 WI
County Scott 154.40
Well Total Depth 4751 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well Gas Well Input Well X SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Petroleum Production Management License Number 6234
Address 200 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 26 Month: 9 Year: 19 91

Plugging proposal received from Steve Park
(company name) Petroleum Production Management (phone) 316-265-4651

were: 4 1/2" at 4750' w/200 sx cement, Perfs at 4642-62' PBD 4704'
1st plug sand back to 3200' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug perforate casing at 1350', pump 145 sx cement,
3rd plug tie into braden head and pump 200 sx cement down backside.

RECEIVED
STATE CORPORATION COMMISSION
OCT 01 1991

Plugging Proposal Received by Steve Pfeifer Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:15 p.m. Day: 26 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3200' and dumped 4 sx cement on top of sand through bailer,
2nd plug perforated at 1350' and pumped 255 sx cement down 4 1/2". Maximum pressure 300 psi and shut in on vacuum.
3rd plug pumped 100 sx cement down 8 5/8" X 4 1/2" annulus. Maximum pressure 350 psi and shut in 100 psi. TOC approx. 450'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(if additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 10-23-91

NO. 33431

Signed Dan Johnson
(TECHNICIAN)