

1 030729

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,337-00-00
SW NE SE, SEC. 25, T 19 S, R 33 W/EX
1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name Eikermann Well # 1

Operator: Dreiling Ltd. of Colorado

County Scott 157.63

Name & Address 410 17th St., Suite 1140

Well Total Depth 4850 Mississippi feet

Denver, Colorado 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling Co., Inc. License Number 9087

Address Box 296, Hays, Kansas 67601

Company to plug at: Hour: 11:30 am Day: 28 Month: July Year: 19 86

Plugging proposal received from John Wise

(company name) R & C (phone) (913) 625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2950'
Anhydrite 2264'

1st plug at the Anhydrite with 50 sx cement

2nd plug at Dakota with 80 sx cement

3rd plug at 30' below surface casing with 40 sx cement

4th plug from 40-0' with 10 sx cement

5th plug to circulate the rat hole with 15 sx cement

6th plug to circulate the mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:45 pm Day: 28 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2264' with 50 sx cement, 2nd plug at 1270' with

80 sx cement, 3rd plug at 410' with 40 sx cement, 4th plug from 40' to surface

with 10 sx cement, 5th plug to circulate the rat hole with 15 sx cement, 6th

plug to circulate the mouse hole with 10 sx cement.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

INVOICED
did not observe this plugging.

DATE AUG - 6 1986

INV. NO. 14609

Signed Steve Durrant
(TECHNICIAN)

AUG 5 1986
08-05-86