

10-24-87

1 061030

API NUMBER 15-171-20,365-60-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

180' W of C
S/2 SE SW, SEC. 25, T 19 S, R 33 W/K

330 feet from S section line
3480 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name Smith Well # 1

Operator: Dreiling Ltd. of Colorado
Name & Address 410 17th Street, #1140
Denver, CO 80202

County Scott 154.18
Well Total Depth 4744 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling Company, Inc. License Number 9087

Address Box 296, Hays, KS 67601

Company to plug at: Hour: 11 a.m. Day: 24 Month: 10 Year: 19 87

Plugging proposal received from John Wise

(company name) R & C Drilling Company, Inc. (phone) 913-625-4548
Elevation 2950' GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2182-2202'
1st plug at 2200' with 50 sx cement, 2nd plug at 1450' with 50 sx cement,
3rd plug at 360' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 p.m. Day: 24 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,
2nd plug at 1450' with 50 sx cement,
3rd plug at 360' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1987
10-29-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

(if not observed this plugging)

DATE 10-30-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 18723

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

CORRECT

(see rules on reverse side)

Starting Date October 16, 1987

API Number 15-171-20,365-00 Location
* 180' West of
C. S2 SE4 SW4 Sec. 25 Twp. 19 S, Rg. 33 X West

OPERATOR: License # 5804
Name Drilling Ltd. Of Colorado
Address 410 - 17th St. # 1140
City/State/Zip Denver, CO 80202
Contact Person Les Olson
Phone 303-623-6144

330 Ft. from South Line of Section
3300 3480 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9087
Name R. and C. Drilling Co., Inc.
City/State Box 296 Hays, KS 67601

Nearest lease or unit boundary line 330 feet
County Scott
Lease Name Smith Well # 1
Ground surface elevation Approx. 2950 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: X yes no
Depth to bottom of fresh water 100' 200'
Depth to bottom of usable water 1350'
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 350'
Conductor pipe required
Projected Total Depth 4750 feet
Formation Mississippian

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 10-6-87 Signature of Operator or Agent Title Operations Manager

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt.
This Authorization Expires 4-12-88 Approved By 10-12-87
EFFECTIVE DATE: 10-17-87

SPUD 10-14-87

PUSHER John Well

TD 4744 FORMATION Mix

SURFACE PIPE 8 1/2" @ 332

ANEHYDRITE 2182 ELEVATION 2950 Gd.

STARTING TIME & DATE 10-14-87 11:00 AM

COMPLETION TIME & DATE 10-24-87 2:15 PM

1st PLUG @ 2200 FT. W/ 570 SX

2nd PLUG @ 1450 FT. W/ 670 SX

3rd PLUG @ 360 FT. W/ 570 SX

4th PLUG @ 40-0 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 1s SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ 60/40 #6 3/8 gals

CEMENT COMPANY Hall

TECHNICIAN Paul Juthie

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1987
CONSERVATION DIVISION
Wichita, Kansas