

1 050221

15-171-00017-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Unknown

C SW NW, SEC. 25, T 19 S, R 33 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050 6814

Lease Name Smith Well # 1-25

Operator: Cargill, Inc.

County Scott

Name & Address Suite 604, One Main Place

Well Total Depth 2695 87.59 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 17 Month: May Year: 1984

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316-938-2348

were: 5 1/2 set at 4704' Perfs 2655 - 70 PRTD 2695

squeezed at 2707' with 150 sx cement

squeezed down 8 5/8 and 5 1/2 annulus with 200 sx cement

Maximum pressure 300 psi

squeezed down 5 1/2 with 1 sack hulls, 10 sx gel, and 110 sx cement Maximum pressure 200psi

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:30 pm Day: 17 Month: May Year: 1984

ACTUAL PLUGGING REPORT 5 1/2 set at 4704' Perfs 2655 - 70 PRTD 2695

squeezed at 2707' with 150 sx cement, squeezed down 8 5/8 and 5 1/2 annulus with 200

sx cement - Maximum pressure 300 psi

squeezed down 5 1/2 with 1 sack hulls, 10 sx gel, and 110 sx cement - Maximum pressure

200 psi

Remarks: No pipe recovery. Use 60/40 Pozmix 2% gel 3% cc by Allied
(if additional description is necessary, use BACK of this form.)

(if applicable) observe this plugging.

INVOICED

DATE 5-25-84

INV. NO. 1648

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1984
CONSERVATION DIVISION
Wichita, Kansas