

1 030742

1666

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,338 00-00

C SE NE, SEC. 17, T 19 S, R 33

3300 feet from S section line

660 feet from E section line

Lease Name Crist Cattle Inc. "B" 1

County Scott 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 467

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.

Name & Address 125 N. Market, Suite 1000

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 617 Union Center Bldg., Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 26 Month: 8 Year: 19 86

Plugging proposal received from Ed McKenna

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2967' GL

1st plug at 2220' with 40 sx of cement

2nd plug at 1320' with 70 sx of cement

3rd plug at 700' with 30 sx of cement

4th plug at 470' with 30 sx of cement

5th plug at 0-40' with 10 sx of cement

6th plug to circulate rathole with 15 sx cement

7th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 26 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2220' with 40 sx cement

2nd plug at 1320' with 70 sx cement

3rd plug at 700' with 30 sx cement

4th plug at 480' with 40 sx cement

5th plug at 40' with 10 sx cement

6th plug to circulate rathole with 10 sx cement

7th plug to circulate mousehole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

Signed *A. Terry* (TECHNICIAN)

DATE 9-3-86

09-03-86
SEP 3 1986

INV. NO. 14871

8-26