

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-011-23869-00-00  
Spot: SWNESWSE Sec/Twnshp/Rge: 17-24S-22E  
825 feet from S Section Line, 1815 feet from E Section Line  
Lease Name: BLYTHE Well #: SK 4  
County: BOURBON Total Vertical Depth: 612 feet

Operator License No.: 33551  
Op Name: S & K OIL PRODUCTION, INC.  
Address: PO BOX 184  
BLUE MOUND, KS 66010

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| SURF   | 6.25 | 20         |             | 5 SX    |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2011 12:00 AM  
Plug Co. License No.: 33551 Plug Co. Name: S & K OIL PRODUCTION, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed 10/29/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran drill pipe to TD. Pumped cement through the drill pipe and placed 10 sacks of cement at TD. Pull drill pipe to 400'. Pumped cement through the drill pipe and placed 10 sacks of cement at 400'. Pulled drill pipe to 200'. Circulated cement through the drill pipe from 200' to surface. Pulled the rest of the drill pipe. Topped well off with cement. A total of 60 sacks of portland cement was reported used to plug this well. Dug down 4' and cut off surface pipe.

RECEIVED

DEC 22 2011 RD

KCC Chanute Dist. #3

RECEIVED  
DEC 30 2011  
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed \_\_\_\_\_

*[Handwritten Signature]*

(TECHNICIAN)

✓ 1/05/12