

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-011-23837-00-00
Spot: SESESWNE Sec/Twnshp/Rge: 18-25S-22E
2805 feet from S Section Line, 1485 feet from E Section Line
Lease Name: PAGE Well #: 6
County: BOURBON Total Vertical Depth: 734 feet

Operator License No.: 33551
Op Name: S & K OIL PRODUCTION, INC.
Address: PO BOX 184
BLUE MOUND, KS 66010

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20		60 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2011 12:00 AM
Plug Co. License No.: 33551 Plug Co. Name: S & K OIL PRODUCTION, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed 09/14/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran drill pipe to TD. Circulated cement through the drill pipe and placed a 50' plug at bottom. Pulled drill pipe up to 400'. Circulated cement through the drill pipe and placed a 50' plug at 400'. Pulled drill pipe to 200'. Circulated cement through the drill pipe from 200' to surface. Pulled rest of the drill pipe and topped well off with cement. A total of 60 sacks of portland cement was reported used to plug this well. Dug down 4' and cut off the surface pipe.

RECEIVED

DEC 22 2011 RD

KCC Chanute Dist. #3

RECEIVED
DEC 30 2011
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed _____

[Signature]
(TECHNICIAN)

1/05/12