

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-27577-00-00
Spot: NWSWNWNE Sec/Twnshp/Rge: 31-29S-20E
775 feet from N Section Line, 2715 feet from W Section Line
Lease Name: SWAYZE, CATHERINE L Well #: 31-1
County: NEOSHO Total Vertical Depth: 586 feet

Operator License No.: 34591
Op Name: SANDY CREEK PETROLEUM, LLC
Address: 1225 EAGLE LANDING DR
COOKEVILLE, TN 38506

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	22		4 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/11/2011 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MICHAEL EBERS Company: SANDY CREEK PETROLEUM Phone: (931) 319-1336

Proposed Plugging Method: Run a cement string to TD and place a cement plug at TD; raise cement string to 200' and fill to surface; gel spacer between.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 10/12/2011 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1" cement string was run to the TD of 586'. The hole was gelled with 3 bags. Two bbls of cement (14 bags) was spotted. The cement string was then raised to 200' and the well filled to surface with 8 bbls (56 bags). Portland cement was used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

DEC 21 2011 AMD

KCC Chanute District

RECEIVED
DEC 30 2011
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

Form CP-2/3

1/05/12