

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-30213-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 27-23S-21E
1237 feet from S Section Line, 1361 feet from E Section Line
Lease Name: GAMLIN Well #: #7
County: ALLEN Total Vertical Depth: 591 feet

Operator License No.: 31519
Op Name: JACKSON, LELAND DBA LONE JACK
Address: 509 E WALNUT ST
BLUE MOUND, KS 66010

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		5 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/07/2011 12:00 AM
Plug Co. License No.: 31519 Plug Co. Name: JACKSON, LELAND DBA LONE JACK OIL CO.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed 09/07/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside 7" surface casing to TD. Pumped 10 sacks of cement through the 1" pipe at TD. Pulled 1" pipe up to 450'. Pumped another 10 sacks of cement through the 1" pipe at 450'. Pulled 250' of 1" pipe to 200'. Circulated another 40 sacks of cement to surface. Pulled remaining 1" pipe. Topped well off. A total of 60 sacks of portland cement was used to plug this well.

RECEIVED

DEC 20 2011 RMD

KCC Chanute Dist #3

RECEIVED
DEC 30 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed _____

[Signature]
(TECHNICIAN)

✓ 1/05/12