

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-011-23843-00-00  
Spot: SESESESW Sec/Twnshp/Rge: 2-24S-21E  
165 feet from S Section Line, 2805 feet from E Section Line  
Lease Name: STEWART Well #: 6-A  
County: BOURBON Total Vertical Depth: 769 feet

Operator License No.: 3728  
Op Name: KENT, ROGER DBA R J ENTERPRISES  
Address: 22082 NE NEOSHO RD  
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		48 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2011 12:00 AM

Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed 07/06/2011 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" inside 7" surface casing to TD. Pumped cement through the 1" pipe and place a 50' plug at TD. Pulled 1" pipe to 400'. Pumped cement through the 1" pipe and placed a 50' plug at 400'. Pulled 1" pipe to 200'. Circulated cement through the 1" pipe from 200' to surface. Pulled the rest of the 1" pipe. Topped well off with cement. A total of 48 sacks of portland cement was reported used to plug this well.

RECEIVED

DEC 22 2011 RD

KCC Chanute Dist. #3

RECEIVED  
DEC 30 2011  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]  
(TECHNICIAN)