

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-30167-00-00
Spot: NENENWNW Sec/Twnshp/Rge: 12-24S-18E
5110 feet from S Section Line, 4130 feet from E Section Line
Lease Name: DEAN KETTLE Well #: WD-1
County: ALLEN Total Vertical Depth: 940 feet

Operator License No.: 5602
Op Name: N & B ENTERPRISES, INC.
Address: PO BOX 812
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20		6 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/20/2011 12:00 AM
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC
Proposal Rcvd. from: N & B ENTERPRISES Company: _____ Phone: (620) 365-9677

Proposed Plugging Method: 10 SACKS ON BOTTOM, 50 SACKS AT 500', CEMENT 250 TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed 05/04/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside 8.625" surface casing to 940'. Pumped 40 sacks of portland cement . Pulled 450' of 1" pipe. Pumped 50 sacks of cement through the 1" pipe. Pulled 250' of 1" pipe. Pumped 25 sacks of cement and circulated to surface. Pulled rest of the 1" pipe. Topped well off. A total of 115 sacks of portland cement was reported used to plug this well.

RECEIVED

DEC 20 2011 RMD

KCC Chanute Dist. #3

RECEIVED
DEC 30 2011
KCC WICHITA

Remarks: _____

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

11/05/12