

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23468-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 30-29S-8E
4006 feet from S Section Line, 8528 feet from E Section Line
Lease Name: YOUNG Well #: 4
County: BUTLER Total Vertical Depth: 2910 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227		145 SX
PROD	4.5	2906		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2011 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM INC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND 50' ABOVE THE TOP PERF @ 2770', W/5 SXS CAP. 50' BELOW SURFACE CASING & CIRC TO SURFACE

Plugging Proposal Received By: DAN FOX Witness Type: NONE
Date/Time Plugging Completed: 12/09/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE TOP PERF @ 2770', DUMP BAILED 5 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 280'-281'. RIH W/ TBG @ 280', GRESSEL OILFIELD MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12-9-2011, 5:00 PM. CEMENT TICKET #37840.

Perfs:

Top	Bot	Thru	Comments
2822	2830	CSG	ARBUCKLE

RECEIVED
DEC 30 2011


KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

1/05/12

1/5K