

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-40279-00-00  
Spot: SESESE Sec/Twnshp/Rge: 23-28S-5E  
242 feet from S Section Line, 254 feet from E Section Line  
Lease Name: NORTH FOX BUSH-SHAWVER Well #: W-15  
County: BUTLER Total Vertical Depth: 2813 feet

Operator License No.: 32475  
Op Name: BRADEN, JAMES R. DBA BRADEN PET  
Address: 10139 SW HAVERHILL RD  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	2500		
PROD	4.5	2723		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/23/2011 8:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: JAMES BRADEN Company: BRADEN PETROLEUM Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/02/2011 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:  
SANDED BACK 50' ABOVE PERFS @ 2670', DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 250'-251'. RIH W/TBG @ 268', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING, RIH W/TBG ON BACKSIDE @ 163', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 275 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12-2-2011, 1:00 PM. CONSOLIDATED CEMENT TICKET #34015. TOPPED WELL BACK TO SURFACE W/30 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2723	2813	OH	OPEN HOLE

RECEIVED  
DEC 30 2011

Remarks: LANDOWNER COMPLAINT / 10 YEAR

KCC WICHITA

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

11/05/12

1/4