

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-001-03163-00-00  
Spot: SENWSWSE Sec/Twnshp/Rge: 9-24S-18E  
750 feet from S Section Line, 2120 feet from E Section Line  
Lease Name: KIRK Well #: 5A/8A  
County: ALLEN Total Vertical Depth: 940 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	20		8 SX
PROD 2		907		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2011 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: JUNE 19, 1952 2" & RAG PACKER SET @ 907' W/ NO CEMENT ON PACKER OR AROUND TUBING. JUNE 10, 1972 RUN 1" TO 934.5' CEMENTED W/ 25 SX CEMENT ON BOTTOM. PULLED 1" OUT LET SET 2 WEEKS RUN 1" BACK IN CEMENT FILL 18' TO 916'. PUMPED 10 SX CEMENT AND PULLED 1" PIPE. 10/28/2011 RUN DOWN ON OUTSIDE TO 600' +/- W/ 1" PUMP CEMENT TO SURFACE. RIH W/ 1" INSIDE 2" PUMP CEMENT TO SURFACE. TOP WELL OFF WELL PLUGGED .

Plugging Proposal Received By: STEVE KORF WitnessType: NONE  
Date/Time Plugging Completed 10/28/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down inside 2" casing to 590'. Tagged cement. Circulated cement through the 1" pipe inside the 2" casing from 590' to surface. Pulled 1" pipe. Ran 1" pipe inside the 8" casing on the outside of the 2" casing to 530'. Circulated cement through the 1" pipe from 530' to surface. Pulled the 1" pipe. Topped well off with cement. A total of 145 sacks of portland cement was reported used to plug this well.

RECEIVED

DEC 21 2011 RMD

KCC Chanute Dist. #3

RECEIVED

DEC 30 2011

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

*[Handwritten Signature]*

(TECHNICIAN)

1/05/12