



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

6-2-82

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
15-071-20, 233-00-00

Dear Sir:

Mr. Russ Cranen of City Service Co. has this date requested permission to plug the following described well:

Operator's Full Name: City Service Company  
Complete Address: 3545 N.W. 58th St. Oklahoma City Okla. 73112  
Lease Name: Loadvine A Well No. 1  
Location: C-5W/4 Sec. 34 Twp. 19 Rge. 39 (E) (E)  
County: Greeley Total Depth: 2910'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereafter indicated: \_\_\_\_\_

Mr. Cranen was instructed to plug the well as follows:

They had 456' of 8 1/8" surface casing cement circulated. They ran 2909' of 4 1/2" production pipes plugged it back to 2886', then perforated 4 1/2" at 2820' to 26'. 1st they set cast iron bridge plug at 2810' + 1 lbs of cement on top of it. 2nd plug at 2020' with 25 lbs of cement. 3rd plug at 500' with 40 lbs of cement. 4th plug at 40' to 0' with 10 lbs of cement. They recovered 2020' of 4 1/2" production

Very truly yours,

Paul A. Luthie  
Conservation Division Agent

JUN 15 1982  
06-1582  
CONSERVATION DIVISION  
Wichita, Kansas

pipe. The cement was pumped through production  
pipe. The plugging was accomplished by Daco  
Lease & well service Co.

Paul A. Lutho