

State of Kansas



15-071-20053-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Floyd Hildreth of Sterling Drilling Company has this
date requested permission to plug the following described well:Mr. Hildreth guarantees payment of the plugging fee.Operator's full Name: Dorchester Exploration, Incorporated,Complete Address: 1204 Vaughn Building, Midland, Texas.Lease Name: Wineinger Well No. A-1Location: CNE/4 Sec. 34 Twp. 19 Rge. (E)(W)40County: Greeley Total Depth 2950' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Hildreth was instructed to plug the well as follows:242'--8 5/8" Surface casing, cement circulated with 160 Ex.
Top of Dakota section @ 875'.Circulate hole with heavy mud. Pull DP to 1100' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent