



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Higginbottom of Dorchester Exploration, Inc., has this date requested permission to plug the following described well:

Mr. Higginbottom guarantees payment of the plugging fee.

Operator's full Name: Dorchester Exploration, Incorporated.

Complete Address: 1204 Vaughn Building, Midland, Texas.

Lease Name: Vogleman Well No. 1

Location: CSE/4 Sec. 8 Twp. 19 Rge. (E)(W) 40

County: Greeley Total Depth 2953' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Higginbottom was instructed to plug the well as follows:

351'--10 3/4" Surface casing, cement circulated with 300 Sx.
2938'--4 1/2" Production casing cemented on bottom with 150 Sx. Perforations from 2906' to 2924' squeezed with 350 Sx. cement. Hole deepened to 2953' with open hole completion.

Run 25 Sx. 50/50 Poz-Mix and displace with plug to plug off bottom.

Shoot casing and pull to 1225' there circulate heavy mud. Pull 4 1/2" casing to 1200' and spot 140 Cu. Ft. cement thru 4 1/2" casing. Pull 4 1/2" to 370' and spot 45 Cu. Ft. cement thru 4 1/2". Pull 4 1/2", set bridge @ 25 w/ 1/2 sack hulls and cement to cellar. Very truly yours,

H. L. Nichols
Conservation Division Agent

TA-WON-74
BPM
DUPLICATOR