



15-071-20004-00-60

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 4 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. W. E. Maxwell of Service Drilling Company, has this date requested permission to plug the following described well:

Mr. Maxwell guarantees payment of the plugging fee.

Operator's full Name: Brooks Hall Oil Corporation,

Complete Address: 1710 Liberty Bank Building, Oklahoma City, Okla.

Lease Name: Thompson Well No. 1

Location: CNE/4 Sec. 28 Twp. 19 Rge. (E)(W) 40

County: Greeley Total Depth 5405 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Maxwell was instructed to plug the well as follows:

103'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1175 and displace 125 Sx.  
cement thru DP. Pull DP to 420' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
 Conservation Division Agent