



15-071-00028-00-00

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ST. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Csg. Pulling has this

date requested permission to plug the following described well:

Hadson Oil & Gas Co.

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Hadson Oil and Gas Company,

Complete Address: 1408 Kermac Building, Oklahoma City, Okla.

Lease Name: K Floyd Well No. 1

Location: CSW-NE Sec. 25 Twp. 19 Rge. (E) (W) 40

County Greeley Total Depth 2881 Oil Well

Gas Well Input Well SWD Well D & A x Lost Hole

Mr. Sargent was instructed to plug the well as follows:

232' -- 8 5/8" Surface pipe, cement circulated.
4 1/2" Production string cemented @ 2881'. Top of cement @ 2476'.
Top perforations @ 2844'.

Squeeze bottom of hole with 10 Sx. cement, leave approximately
100' in casing above top perforations. Bridge hole at top of
fluid if below 350' and set 20 Sx. cement. Fill hole with mud
to 230' and set 20 Sx. cement. Fill hole with mud to 35', set
bridge and 10 Sx. cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

JUN 28 1965

Conservation Division Agent

CONSERVATION DIVISION
WICHITA, KANSAS