

State of Kansas



15-071-20020-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Dorchester Exploration Company,

Complete Address: 1204 Vaughn Building, Midland, Texas.

Lease Name: Campbell Well No. 1

Location: CSE Sec. 13 Twp. 19 Rge. (E)(W) 41

County: Greeley Total Depth 2930' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

364'--10 3/4" Surface casing, cement circulated with 300 Sx. (9" Hole).
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1240' and displace 140 Cu. Ft.
cement thru DP. Pull DP to 400' and displace 40 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1 sack hulls and 20 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent