

15-171-00059-00-00

HARRIS "A" NO. 1

NE/4 NW/4 SE/4 Sec. 25-18S-33W, Scott County, Kansas

Rigging up Rotary Tools 4-20-50
Tearing down Rotary Tools 5-27-50

Run 13 Jts. 10 3/4" surface pipe. Set at 270' and cemented with 150 sacks cement.
Run 165 Jts. 4786' of 5 1/2" casing. Set at 4783' and cemented with 75 sacks cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Gravel	0	70
Gravel and sand	70	272
Sand, shale and clay	272	475
Shale and gumbo	475	1225
Shale and shells	1225	1425
Redbed and shale	1425	1740
Shale and salt	1740	1790
Shale and shells	1790	1800
Red rock and sand	1800	2200
Red bed, shale and shells	2200	2495
Shale and shells	2495	2640
Shale and red rock	2640	2765
Shale and lime	2765	2995
Shale, lime and sand	2995	3040
Shale and lime	3040	3184
Lime	3184	3370
Lime and shale	3370	3565
Lime	3565	3770
Lime and shale	3770	3960
Lime	3960	4085
Lime and shale	4085	4115
Lime	4115	4280
Lime and shale	4280	4335
Lime	4335	4395
Lime and shale	4395	4450
Lime	4450	4475
Shale and lime	4475	4580
Lime	4580	4780
Shale and lime	4780	4793 Total Depth

RECEIVED
JUL 24 1950
STATE REGISTRATION
COMMISSION
KANSAS

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 17th day of July, 1950.

William Kelly
Notary Public

My commission expires March 22, 1952.

PLUGGING
FILE SEC 25 T 18 R 33W
BOOK PAGE 17 LINE 8

SHALLOW WATER
GARDEN CITY
RECEIVED
JUL 18 1950
7:19:10:11:12:13:14:15:16:17:18:19