



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 2 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 04-02-68

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company,

Complete Address: Box #2585, Amarillo, Texas.

Lease Name: Spitzer Well No. 1

Location: NE-NE, 560' FNL-660' FEL Sec. 13 Twp. 19 Rge. (E)(W) 31

County: Scott Total Depth 4840' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

253'--8 5/8" Surface pipe, cement circulated with 225 Sx.  
Dakota Section Top @ 900'.

Circulate hole with heavy mud. Pull DP to 110' and displace 100 Sx.  
cement thru DP. Pull DP to 270' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

*M. L. Nichols*  
 Conservation Division Agent