



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

18-May-1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
15-171-20,234-00-00

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1982  
05-25-82  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Harold Maley of Abscon Oil Drilling, Inc. has

date requested permission to plug the following described well:

Operator's Full Name: American Energy Corp.

Complete Address: 575 Fourth Financial Ctr. Wichita, Kansas 67202

Lease Name: Burke Well No. 1

Location: C-SE-NW-NE Sec. 10 Twp. 19 Rge. 31 (E) (W)

County: Scott Total Depth: 4658'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: .. \_\_\_\_\_

Mr. Maley was instructed to plug the well as follows:

They cement circulated 328' of 8 7/8" casing with 275 sbs of common cement with 3 yds 2 1/2 cc. The anhydrite was topped at 2286'. The Dakota was topped at 1000'. 1st plug at 2200' with 35 sbs of cement. 2nd plug at 1090' with 35 sbs of cement. 3rd plug at 360' with 20 sbs of cement. 4th at 40' to 0' with 10 sbs of cement. Then circulated 10 sbs of cement in rat hole. The cement was pumped through (over)

Very truly yours,

Paul A. Luthi  
Conservation Division Agent

Drill pipe with hole full of heavy mud. The plugging  
was accomplished by sun cementing.

Paul A. Latti