

corrected

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34510 Name: Bayswater Exploration and Production, LLC Address 1: 730 17th Street, Suite 610 City: Denver State: CO Zip: 80202 Contact Person: Kevin Kane Phone: (303) 893-2503 Ext. 216 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet)

API No. 15 - 199-20390-00-00 Spot Description: SW SE SW Sec. 33 Twp. 15 S. R. 40 East West 344 Feet from North South Line of Section 1,691 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Wallace Lease Name: Ray Smith 24-33 Well #: 1 Date Well Completed: The plugging proposal was approved on: 3/8/2011 by: Pat Staab (KCC District Agent's Name) Plugging Commenced: 3/10/2011 Plugging Completed: 3/10/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8" 24#/ft, 365', No.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up, Pre job safety meeting/Pump 1st Plug 25 sks 2700' to 2589' (111') TOH & LD Dp Pump 2nd plug 100 sks 1680' to 1234' (446') TOH & LD Dp Pump 3rd plug 50 sks 415' to 236' (178') Pump top plug 10sks 40' to surface (45') / cement rat hole 30 sks, mouse hole 15 sks Circulated cement on top plug & both rat & mouse holes 220 total sks Class A, 60/40 Poz mix 4%gel 1/4# flocele wt.13.8 yield 1.41

RECEIVED NOV 29 2011 KCC WICHITA

Plugging Contractor License #: 99996 Name: Allied Cementing Co., LLC Address 1: 24 S. Lincoln Street Address 2: P.O. Box 31 City: Russell State: KS Zip: 67665 + 2906 Phone: (785) 483-3887

Name of Party Responsible for Plugging Fees: Bayswater Exploration and Production State of Colorado County, Denver, ss. Kevin Kane (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

AP