

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5145
Name: Dreiling Oil, Inc.
Address 1: P.O. Box 550
Address 2: _____
City: Hays State: Ks. Zip: 67601 + 0550
Contact Person: Terry W. Piesker
Phone: (785) 625-8327
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3542' Bottom: 3545' T.D. 3544'
L-KC Depth to Top: 3289' Bottom: 3381' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-19297-00-00
Spot Description: _____
NE, NE, NW Sec. 10 Twp. 13 S. R. 17 East West
330 4950 Feet from North / South Line of Section
2340 2970 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Karlin Well #: 2
Date Well Completed: 6-27-63
The plugging proposal was approved on: 11-17-11 (Date)
by: Marvin Mills (KCC District Agent's Name)
Plugging Commenced: 11-22-11
Plugging Completed: 11-22-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	Oil and water	Surface	8 5/8"	144'	none
L-KC	Oil and water	Production	4 1/2"	3544'	None
	Several Squeeze Jobs-	700' to 950' with 250 sx.	2088' to 2552' 150 sx.	2460' to 2490' 150 sx.	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran Tubing to 3500' and mixed 110 sxs. 60/40 Poz, 4% gel and 200# hulls. Pulled up to 2100' and mixed 135 sxs. of same with 200# Hulls and cement circulated. Pulled Tubing and tied to 8 5/8" Casing and mixed 10 sxs. and came around to 4 1/2" Casing. Loaded 4 1/2" Casing with 15 more sxs. of same.

Plugging Contractor License #: 99996 Name: Allied Cementing and Acidizing, Inc.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + _____
Phone: (_____) _____
Name of Party Responsible for Plugging Fees: Dreiling Oil, Inc.
State of Kansas County, Ellis, ss.
Terry W. Piesker Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry W. Piesker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 29 2011
KCC WICHITA