

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior Inc.  
Address 1: P.O. Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: Ks. Zip: 67846 + \_\_\_\_\_  
Contact Person: Jody Smith  
Phone: (620) 272-2963  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L/KC Depth to Top: 3436 Bottom: 3440 T.D. 3657'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 051-24174 · 00 · 00  
Spot Description: \_\_\_\_\_  
C SW SW NE Sec. 18 Twp. 14 S. R. 18  East  West  
2,961 Feet from  North /  South Line of Section  
2,393 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: State of Kansas Well #: A-1  
Date Well Completed: 4/4/85  
The plugging proposal was approved on: 11/7/11 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Plugging Commenced: 11/28/11  
Plugging Completed: 11/28/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
K/C C	oil	Surface	85/8	498'	0
		Production	41/2	3670'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP@ 3285'. Log Tech perf 1850', 1365' and 650', 2spf. Ran tbg to 3000'. Swift hooked up to tbg, mixed and pumped 150sx 60/40 poz 4% gel w/ 300# hulls and displaced. Pulled tbg to 800', Swift hooked up to tbg, Mixed and pumped 20sx 60/40 poz 4% gel w/ 20# hulls, Circulated cement to surface, closed in 41/2, Mixed and pumped 100sx 60/40 poz 4% gel w/55# hulls, Circulated cement out 85/8. Pulled tbg. Toped 41/2 off w/ 30sx 60/40 poz 4% gel, Pressure 41/2 to 250# Moved off.

Plugging Contractor License #: 32382 Name: Swift Services, Inc.  
Address 1: P.O. Box 466 Address 2: \_\_\_\_\_  
City: Ness City State: Ks Zip: 67560  
Phone: (785) 798-2300  
Name of Party Responsible for Plugging Fees: American Warrior Inc.  
State of Kansas County, Finney, ss.  
Jody Smith  Employee of Operator or  Operator on above-described well,  
(Print Name)

RECEIVED  
NOV 30 2011

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Ax