

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior Inc.
Address 1: P.O. Box 399
Address 2: _____
City: Garden City State: Ks. Zip: 67846 + _____
Contact Person: Jody Smith
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: 3552' Bottom: 3576' T.D. 3751'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 185-10805 • 00 • 00
Spot Description: _____
C W/2 NE SW Sec. 27 Twp. 21 S. R. 14 East West
2,027 Feet from North / South Line of Section
3,609 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: Gates Well #: B-5
Date Well Completed: 3/8/52
The plugging proposal was approved on: 11/29/11 (Date)
by: Make Maier (KCC District Agent's Name)
Plugging Commenced: 11/29/11
Plugging Completed: 11/29/11

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>L/KC</u>	<u>oil</u>	<u>Surface</u>	<u>85/8</u>	<u>275</u>	<u>0</u>
		<u>Production</u>	<u>51/2</u>	<u>3749</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech set CIBP@3480'w/2sx cement and perf 780',2spf. Ran tbg to 794'. Swift hooked up to tbg, Mixed and pumped 100sx 60/40 poz 4% gel. Cement circulated to surface. Pulled tbg. Swift hooked up to 85/8, Mixed and pumped 20sx 60/40 poz 4% gel. Swift topped 51/2 off w/ 10sx 60/40 pox 4% gel.

Plugging Contractor License #: 32382 Name: Swift Services, Inc.
Address 1: P.O. Box 466 Address 2: _____
City: Ness City State: Ks Zip: 67560 + _____
Phone: (785) 798-2300
Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.
Jody Smith Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

RECEIVED
DEC 01 2011