

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9810
Name: McElvain Energy, Inc.
Address 1: 1050 - 17th Street
Address 2: Suite 2500
City: Denver State: CO Zip: 80265 + 2080
Contact Person: E. Reed Fischer
Phone: (303) 893-0933 xtn 330
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 5654 Bottom: 5676 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 187-20915 · 00 · 00
Spot Description: _____
SW_NW_SE _____ Sec. 22 Twp. 30 S. R. 39 East West
1,370 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stanton
Lease Name: Shore Well #: 1-1022
Date Well Completed: March 10, 1999
The plugging proposal was approved on: Sept. 19, 2011 (Date)
by: Ken Hemlick (KCC District Agent's Name)
Plugging Commenced: October 10, 2011
Plugging Completed: October 11, 2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Marmaton (4910-5090')	Water	Surface	8.625", 24#	1765	None
Atoka (5090-5215')	Water	Production	4.50", 10.5#	5800	None
Morrow (5215-5690')	Oil, Gas & Water				
Chester (5690-TD)	Water				


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

PLUG #1 (5325-5620') - 20 sx Type 'C' cmt pumped thru 2.375" tubing on top of CIBP @ 5620.
Pumped 9 ppg plug mud pumped thru tubing above Plug # 1 to 3,000'.
PLUG # 2 (2950-2975') - 2 sx Neat cmt dumped on top of wireline set CIBP @ 2975' after pressure testing CIBP down casing to 500 psi.
PLUG # 3 (1595-1826') Annular Plug - 40 sx Type 'C' cmt pumped down 4.5" casing thru squeeze holes @ 1825-1826, preceded by 15 bbbs of 9 ppg plug mud and followed by 10 frac balls.
PLUG # 3 (1165-1826') Inside Plug - 45 sx Type 'C' cmt pumped after frac balls down 4.5" casing. Displaced with 19 bbbs plug mud until ball out.
PLUG # 4 (Surface-801') Both inside 4.5" casing and between 4.5"x8.625" annulus - 155 sx Type 'C' cmt pumped down 4.5" and thru squeeze holes from 600-601'. 20 sx cement returned to surface. Following wellhead cut-off 8' below ground level on October 18, 2011, another 10 sx of cement were used to top-off 4.5" casing before welding a plate over casing stubs inscribed with Operator name and date.
Total of 260 sx Type 'C' cement (1.32 ft3/sk Yield) supplied by Allied Oil & Gas Services were pumped for PLUGs # 1, 3 & 4, plus 2 sacks neat cement (1.15 ft3/sk Yield) supplied & dumped by Weatherford for Plug # 2 plus another 10 sacks cement supplied by Treco Inc. for surface top-off following wellhead cut-off.
Plug set operations were witnessed by Ken Hemlick from KCC.

Plugging Contractor License #: 99996 Name: Allied Oil & Gas Services, LLC
Address 1: 24 S. Lincoln Street Address 2: P.O. Box 31
City: Russell State: Kansas Zip: 67665 + 2906
Phone: (817) 546-7282
Name of Party Responsible for Plugging Fees: McElvain Energy, Inc.

State of Colorado County, Denver, ss.
E. Reed Fischer Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 02 2011

12-2-11
KCC WICHITA

LR