

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-5-117

API NUMBER 15-175-20,431-000

LEASE NAME Hitch Unit

WELL NUMBER 2-1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 10 TWP. 33S RGE. 34 (E) or (W)

COUNTY Seward

Date Well Completed 2-26-80

Plugging Commenced 2-1-94

Plugging Completed 2-3-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-30-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? previously submitted

Producing Formation L. Chester Depth to Top 6152 Bottom 6176 T.O. 6277

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1649	0
				5 1/2	6276	2111

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pmp 1 sk hulls & 25 sxs cmt 6176-5700. Shot 2111, pmp 40 sxs cmt 2100-1950, pmp 50 sxs cmt 1690-1590, pmp 30 sxs cmt 650-550, pmp 10 sxs 40-0. Cut off & capped 3' below ground level.
Restore location. KCC Rep - Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1 Box 49BA, Tyrone, Oklahoma 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Tech. Asst.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 8th day of March 1994

My Commission Expires:



Notary Public

RECEIVED
CORPORATION DIVISION
3-10-94
Wichita, Kansas
Form CP-4
Revised 05-88