

15775-20652-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Seward SEC. 10 TWP. 33S RGE. 34 W
 Location as in quarters or footage from lines:
330' E of Center, NE/4

Lease Owner Anadarko Production Company
 Lease Name Hitch "I" Well No. 3
 Office Address Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 8/30/82
 Application for plugging filed 9/3/82
 Plugging commenced 8/30/82
 Plugging completed 8/30/82
 Reason for abandonment of well or producing formation Dry

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Bob Tarbutton
 Producing formation _____ Depth to top _____ bottom T.D. 6310
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	1636	0

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

70 sxs plug at 3150', 60 sxs @ 1650', 60 sxs @ 600', 10 sxs 40-0', with 1/2 sxs Halls
+ wooden plug. 10 sxs in rathole, 5 sxs in mousehole.
Heavy drilling mud between each plug.
Cmt - 50/50 Poz 4% gel, 3% CaCl.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 10 1982
 9-10-82
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Paul Campbell (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1982

My Commission expires:

ELIZABETH J. HOOPER
 Seward County, Kansas
 My Appt. Expires 7-26-83

Elizabeth J. Hooper
 Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Hitch "I-#3"
 1320' FNL & 990' FEL Sec 10-33S-34W
 Seward County Kansas

Commenced: 8-17-82

Completed: 8-29-82

OPERATOR: ANADARKO PRODUCTION CO.

Depth		Formation	Remarks
From	To		
0	339	Sand-Redbed	
339	1258	Sand-Redbed-Anhy	Ran 40 jts of 24# 8 5/8"
1258	1603	Redbed-Sand-Anhy	csg set @ 1636' Cemented
1603	1705	Sand-Redbed-Anhy	w/600 sks Posmix 4% Gel
1705	6310	Lime-Shale	2% CC + 225 sks Common
	6310 - TD		2% CC PD @ 4:00 a.m. 8-19-82
			DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' WELL Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 2nd day of September, 1982.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 10 1982
 CONSERVATION DIVISION
 Wichita, Kansas

