

15-035-19484-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Cowley County, Sec. 28 Twp. 34S Rge. 3E (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Crest Petroleum, Inc.

Lease Name Jones Estate Well No. 1

Office Address 2700 E. Central, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed October 30 19 53

Application for plugging filed March 14 19 57

Application for plugging approved March 15 19 57

Plugging commenced April 1 19 57

Plugging completed April 1 19 57

Reason for abandonment of well or producing formation not commercial

If a producing well is abandoned, date of last production Feb. 7, 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. S. Lemaster

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3413 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	96 ft.	none
				5-1/2"	3413 ft	2187.51 ft

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Dumped cement from 3413 to 3272 feet;
Filled with mud from 3272 to 200 feet;
Set rock bridge (15') 200 to 185 feet;
Dumped cement from 185 to 140 feet;
Filled hole with mud from 140 to 40 feet;
Filled with cement from 40 feet to surface;
and welded steel cap on top of surface pipe to complete.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1957
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Butler County Drilling Co.

Address 506 Orpheum Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
W. W. Wright (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2700 E. Central, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 57

My commission expires January 28, 1959. Annette K. Smith Notary Public.

PLUGGING
FILE SEC 28 T 34 R 3E
BOOK PAGE 148 LINE 26

COMPANY: Crest Petroleum, et al
 CONTRACTOR: Fortier & Wright Drilling Co.
 FARM: Jones Estate No. 1
 LOCATION: NW NW NW, Section 28-34S-3E
 Cowley County, Kansas

COMMENCED: September 28, 1953
 COMPLETED: October 27, 1953

ELEVATION: 1138 Gr (1140 D.F.)

All measurements from rotary bushing
 2 1/2 feet above derrick floor.

CASING RECORD: 8-5/8" cemented at 96 feet w/70 sacks
 5-1/2" cemented at 3412 w/75 sacks

FORMATION	DEPTH
Soil - Sub-soil	58
Shale - Lime	80
Lime	96
Lime - Red bed - Lime	910
Shale - Shells	1275
Lime - Shale	1450
Sand - Shale	1640
Shale	1840
Lime - Shale	1945
Lime - Shale	2030
Shale	2232
Shale Sand - Shale Stalnaker	2355
Sandy shale	2470
Shale	2672
Sand Layton	2700
Layton Sand - Shale	2820
Shale - Kansas City Lime	2940
Lime - Shale - Sand	3060
Lime - Shale	3125
Oswego Lime	3170
Lime - Shale	3250
Shale	3375
Rotary Total Depth	3414

TOPS	
Stalnaker sand	2355
Layton sand	2700
Kansas City Lime	2940
Oswego Lime	3170

Perforated 47 shts 3370-3390

I hereby certify that this is a true and correct record and log of the well drilled on the above-mentioned location to the best of my knowledge and belief.

FORTIER & WRIGHT DRILLING CO.

By 

STATE OF KANSAS
 ss
 COUNTY OF SEDGWICK

RECEIVED
 STATE CORPORATION COMMISSION

MAR 15 1957

Subscribed and sworn to before me this 4th day of December, 1953,
 as a Notary Public, within and for the said County and State above.

My Commission Expires: 1/19/1955

PLUGGING
 FILE - SEC. 28 T. 34 R. 3E
 BOOK PAGE 148 LINE 26

Annette A. Kennally
 Notary Public