

RECEIVED

WELL PLUGGING APPLICATION FORM JAN 06 1994
(PLEASE TYPE FORM and File ONE Copy)

API AS 175-20,431 (Identifier number of this well listed for wells drilled since 1967; if no API# was issued, indicate spud/completion date.)

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Hitch Unit WELL# 2-1 SEC. 10 T. 33S R. 34 (~~East~~/West)

- C - NE - NE SPOT LOCATION/QQQQ COUNTY Seward

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE NA SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1649' CEMENTED WITH 800 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 6276' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 6152-6176'

ELEVATION 2879' T.D. 6277' PBSD 6183' ANHYDRITE DEPTH 1630'
(G.L./~~XXBX~~) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Ld hole w/9 ppg mud & establish injection dwn 5 1/2" csg. Spot 2 sxs hulls & 20 sxs cmt @ 6183-6102'. Cut 5 1/2 csg @ 5000' and salvage. Spot 15 sxs in 8 5/8" csg @ 40-3'. Cut 8 5/8 csg off 3' below ground level and cap. Restore location.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? previously submitted IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE# (316) 624-6253

ADDRESS P.O. Box 351 City/State Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent & Horton Plugging Inc. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS Rt 1 Box 49-BA, Tyrone, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/30/93 AUTHORIZED OPERATOR/AGENT: Daniel Kapple
(signature)

J. L. Ashton, Division Production Manager

ANADARKO PETROLEUM CORPORATION

PHONE 316-624-6253 • 2330 NORTH KANSAS AVE. • P.O. BOX 351 • LIBERAL, KANSAS 67905-0351



January 4, 1994

Kansas Corporation Commission
Conservation Division
200 Colorado Derby Building
Wichita, Kansas 67202

Attn: Priscilla Zadoka

Re: Plug and Abandonment
Hitch Unit #1-11
1400' FSL & 1600' FEL
Section 3-33S-34W
Seward County, Kansas

Hitch Unit #2-1
C NE NE
Section 10-33S-34W
Seward County, Kansas

Dear Ms. Zadoka:

Enclosed in duplicate is the "Well Plugging Application" (KCC Form CP-1) for the above referenced wells. These forms are to renew the expired applications dated July 15, 1993.

Very truly yours,

A handwritten signature in cursive script that reads "David Kappeler for". The signature is written in dark ink and is positioned above the typed name of the sender.

J. L. Ashton
Division Production Manager
CLM-BJW/cs

Enclosures

cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
Ellen Cobb - HGO
WI Owners
Sargent & Horton Plugging Inc.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 06 1994
CONSERVATION DIVISION
WICHITA, KS



Kansas Corporation Commission

Joan Finney, Governor Jim Robinson, Chairman F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 6, 1994

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Hitch Unit #2-1
API 15-175-20, 431-00 @
660 FNL 660 FEL
Sec. 10-33S-34W
Seward County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760