

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20516-00-00  
Spot: SE Sec/Twnshp/Rge: 3-29S-8W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: JANE T WALTER Well #: 1  
County: KINGMAN Total Vertical Depth: 4145 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DR STE 204  
WESTMONT, IL 60559

| String | Size  | Depth (ft) | Pulled (ft) | Comments    |
|--------|-------|------------|-------------|-------------|
| SURF   | 8.625 | 208        |             | 225 SXS CMT |
| PROD   | 4.5   | 4135       | 1446        | 125 SXS CMT |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2011 8:00 AM  
Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.  
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPL Phone: (620) 786-9166

Proposed Plugging Method: CIBP 4080 & 2 SKS CMT. 35 SX 1200, 35 SX 800, CIRC 280-0

Plugging Proposal Received By: B. J. HOPE Witness Type: NONE  
Date/Time Plugging Completed: 06/29/2011 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4080' & CAPPED WITH 4 SKS CMT. RECOVERED 1446' OF 4 1/2".  
RAN TUBING TO 1208' & SPOTTED 50 SX CMT. PULLED TUBING TO 790' &  
SPOTTED 50 SX CMT. PULLED TO 270' & CIRC CEMENT TO SURFACE.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4135 | 4145 | OH   |          |

Remarks: ALLIED CMT 60/40 4% GEL

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED Form CP-2/3  
DEC 16 2011 12/23/11

KCC WICHITA